




U.S. DEPARTMENT OF  
**ENERGY**



# Hydrogen Delivery - Session Introduction -

*Scott Weil*

2012 Annual Merit Review and Peer Evaluation Meeting  
May 17, 2012

# Delivery Sub-Program Goal

- Improve fuel cell electric vehicle competitiveness by reducing the cost of producing, delivering, and dispensing H<sub>2</sub> to below a threshold of \$2-\$4/kg H<sub>2</sub> by 2020
- Delivery sub-program target: reduce the “Delivery” portion of this cost to \$1 – 2/kg by 2020

Tube trailer gas transport



Liquid transport



Pipeline transmission




Fueling stations

Delivery Element	2011 Status*	Goal (2015 Targets)**
Tube trailers	<ul style="list-style-type: none"> <li>Capital cost: \$930/kg of H<sub>2</sub> transported (180 bar steel vessels)</li> <li>Capacity: ~300kg (180 bar steel vessels)</li> </ul>	<ul style="list-style-type: none"> <li>Reduce capital cost 22% to &lt; \$730/kg of H<sub>2</sub> transported</li> <li>Increase capacity &gt;1.3x to 700kg</li> </ul>
Large Scale Liquefaction	<ul style="list-style-type: none"> <li>Installed capital cost: \$190M</li> <li>Process energy required: &gt;8kWh/kg of H<sub>2</sub></li> </ul>	<ul style="list-style-type: none"> <li>Reduce installed capital cost 21% to \$150M</li> <li>Reduce process energy required 12% to 7kWh/kg of H<sub>2</sub></li> </ul>
Pipeline technology	<ul style="list-style-type: none"> <li>Installed steel pipeline cost: \$765K/mi on average</li> </ul>	<ul style="list-style-type: none"> <li>Reduce cost/mile (installed 8" equivalent diameter, excluding ROW) 4% to &lt;\$735K/mi</li> </ul>
Forecourt compression (1000 kg/day station)	<ul style="list-style-type: none"> <li>Capital cost: \$450K for two 860 bar compressors (each rated at 50% of peak flow)</li> </ul>	<ul style="list-style-type: none"> <li>Reduce installed capital cost 11% to \$400K for two 860 bar compressors (each rated at 50% of peak flow)</li> </ul>
Forecourt storage (1000 kg/day station)	<ul style="list-style-type: none"> <li>Storage tank cost: \$1000/kg H<sub>2</sub>, \$1100/kg H<sub>2</sub>, and \$1450/kg H<sub>2</sub> respectively for 160, 430, and 860 bar storage.</li> </ul>	<ul style="list-style-type: none"> <li>Reduce tank cost/kg H<sub>2</sub> stored by 14-18% to \$850, \$900, and \$1200/kg H<sub>2</sub> for low, moderate, and high pressure storage (160, 430, and 850 bar respectively).</li> </ul>

\* High volume projections based on the latest data employed in HDSAM (v. 2.3) – in final review.

\*\* Based on the new DOE-FCTP MYRD&D technical targets for Delivery – in final review.

- **Early market scenario: Tube trailers & Forecourt technology:**
  - ▶ Shift in emphasis to near-term H<sub>2</sub> infrastructure needs
  - ▶ **Cost, reliability, and efficiency of station compressors**
  - ▶ Possible trade-offs between delivered pressure and forecourt compression (cost)
  - ▶ Tube trailer vessel capacity
  - ▶ Regulatory issues with transportation of high-pressure transport vessels




## **Early/mid-term market scenarios: Liquid H<sub>2</sub> delivery & Forecourt technology**

- ▶ Energy efficiency of liquefaction: emissions under current US grid sources
- ▶ Transfer boil off
- ▶ Capital cost
- **Long-term market scenario: Pipelines**
  - ▶ Managing embrittlement (steel pipelines) to reduce lifetime cost
  - ▶ Capital, installation, and right-of-way costs
  - ▶ Hydrogen quality
  - ▶ Bulk storage (geologic)
- **Cross-cutting issues:**
  - ▶ Fuel cost vs. purity standards
  - ▶ Vehicle range vs. storage pressure & its impact on delivery cost
  - ▶ Production pressure vs. station compression needs
  - ▶ Impact of code requirements on transport and station costs

**FY 2012 Appropriation = \$5.2M**

**FY 2013 Request = \$2.9M**




## EMPHASIS

- **Pathway cost analyses**
  - ▶ Cost reduction options for near- and mid-term infrastructure development timeframes
- **Reduce forecourt cost**
  - ▶ Improved compressor durability
  - ▶ Reduced storage cost
  - ▶ Reduction in station compression needs
- **Reduce tube trailer gas delivery cost**
  - ▶ Maximize transport capacity at constant or reduced \$/kg of H<sub>2</sub> transported
- **Increase the efficiency of H<sub>2</sub> liquefaction**
  - ▶ High efficiency magnetic cooling
- **Reduce pipeline delivery cost**
  - ▶ Centrifugal pipeline compressors – reduced system cost and improved reliability
  - ▶ Fiber reinforced polymer pipeline – reduced installation cost

**Challenge:** Identify key cost factors in various Delivery pathways & evaluate options to reduce cost over various market scenarios

**Progress:** (1) New HDSAM version (v2.3) is complete & on-line and (2) evaluating potential benefits of moving compression upstream

100 kg/hr capacity (typical for 1000 kg/day station)



PIs: ANL, PNNL, NREL, consultant

- **Issues with compressors:**
  - ▶ High capital cost per unit of throughput
  - ▶ Underutilization of capital in early markets
  - ▶ High power demand (electrical upgrades)
  - ▶ Limited fill rate without significant cooling
- **Potential solution: Move capital upstream of the refueling station:**
  - ▶ Better utilization (multiple markets)
  - ▶ Economies of scale
  - ▶ Risk is distributed between different market segments/applications

**Challenge:** *High refueling station costs may impede commercial investment in early motive markets (MHE and FCVs)*

**Progress:** *(1) Projected reduction in station storage costs of 11% (61% to 2015 targets) and (2) evaluating more durable approaches to compression*

## Past Year's Accomplishments

- ORNL initiated a series of design trade studies and preliminary cost estimates of their steel-lined reinforced concrete station vessel concept
- FuelCell Energy (FCE) validated 2-stage electrochemical compressor (EHC) hardware feasibility at 7,000 psi level and increased H<sub>2</sub> flux 40% above their Gen 1 design

## Recent Accomplishments

- ORNL – completed engineering calculations, manufacturing process flow, and cost assessment for composite vessel design options
- NREL developed a test protocol for real-time monitoring of power use (on-going) in Linde's new ionic compressor at AC Transit Emeryville station
- FCE achieved 12,000 psi (820 bar) in a single stage EHC unit (800:1 compression ratio)


## Future Work

- Optimize vessel designs for cost reduction and verify code compliance via structural analysis
- Reduce EHC stack part count by 30% and validate baseline stack performance (5 cells)

PIs: ORNL, FuelCell Energy, NREL



Linde



*Challenges: Reduce tube trailer delivery cost by 13 and 32% respectively to meet the 2015 and 2020 cost targets for tube trailer delivery*

*Progress: New design meets 2015 capacity target at a projected cost of \$750/kg of H<sub>2</sub> transported (80% to 2015 target)*

## Past Year's Accomplishments

- Completed a design trade study on carbon fiber wrapped vessels :
  - ▶ Vessel pressure can be increased an additional 100 bar (350 bar)
  - ▶ Carrying capacity can be increased an additional 33% (800 kg H<sub>2</sub>)
  - ▶ Transport cost can be reduced another 10%
- Successfully fabricated and hydroburst tested a full-scale glass fiber wrapped vessel

## Recent Accomplishments

- Received DOT special permit approval for Titan™
- Designed and delivered a trailer capable of holding 5 large cylinders
  - ▶ 18% increase in volume capacity compared to 4 cylinder module
- Developed a fault tree map for fiber composite pressure vessels

## Future Work

- Qualify TITAN 5™ system components for CHG:
  - ▶ Fire protection components
  - ▶ Valves and manifolds
- Draft a detailed report on the status and future viability of the cold gas transport option

TITAN 5™



Lincoln Composites

PIs: Lincoln Composites and LLNL

**Challenges:** *Increased liquefaction efficiency*

**Progress:** *Phase 1 demonstration of a system with the potential to reduce energy consumption by 32% (meets 2020 target)*

## Past Year's Accomplishments


- Improved ortho-para conversion performance with a catalyst – reduces total power required for liquefaction by 2.4%
- Fabricated a continuous catalytic heat exchanger for testing – projected to improve performance
- Fabricated all sub-systems for a prototype active magnetic regenerative refrigerator (AMRR)

## Recent Accomplishments

- Passed Phase 1 objectives for magnetic liquefaction prototype
  - ▶ Integrated all sub-systems into a working prototype AMRR device
  - ▶ Achieved <240K with the prototype AMRR

## Future Work

- Phase 2 – demonstrate cooling down to 120K, incorporating a bypass flow modification to the system



PI: Heracles Energy Corp.

**Challenges:**  $H_2$  embrittlement of pipeline steel & the cost of pipeline infrastructure and large-scale gas compression are significant economic barriers


**Progress:** FRP pipeline codification process started (FRP meets 2015 cost target) and compressor CapEx reduction of 20% (67% to 2020 target)

## Past Year's Accomplishments

- Developed models to simulate the effects of  $H_2$  on the mechanical properties of pipeline steels
- Demonstrated a 3x design margin for FRP through flaw tolerance testing
- Completed detailed design and thermomechanical analyses of two prototype centrifugal compressor concepts

## Recent Accomplishments

- Established protocols with codes committees to develop performance qualification test methodology for FRP pipeline
- Observed that  $>10\text{ppm } O_2$  retards fatigue crack growth in pipeline steel exposed to  $H_2$
- Fabricated key components for two single-stage centrifugal compressors units that will undergo operational testing




Concepts NREC

## Future Work

- Perform full life fatigue and stress rupture testing for FRP piping.
- Expand pipeline steel testing beyond X52 to higher-strength steels, such as X70 and X80
- Finish compressor prototype builds and carry out system shakedown tests

## Major milestones & Future Solicitations

- Published update version of HDSAM (v 2.3), completed new sub-program targets, and initiated early market optimization analysis
- Met 2015 target for tube trailer vessel capacity
- Single stage prototype centrifugal compressor systems being fabricated for testing
- Passed phase 1 objectives for magnetic liquefaction prototype
- Established protocols with codes committees to develop performance qualification test methodology for FRP pipeline
- *Identify technologies and optimized delivery pathway options that meet an as-dispensed H<sub>2</sub> cost of <\$4/gge*
- *Complete technical and economic characterization and analysis of novel compression options that have the potential to reduce current refueling station costs by a minimum of 15%.*



\*subject to appropriations

- This is a review, not a conference.
- Presentations will begin precisely at scheduled times.
- Talks will be 20 minutes and Q&A 10 minutes.
- Reviewers have priority for questions over the general audience.
- Reviewers should be seated in front of the room for convenient access by the microphone attendants during the Q&A.
- Please mute all cell phones and other portable devices.
- Photography and audio and video recording are not permitted.

- Deadline to submit your reviews is **May 25<sup>th</sup> at 5:00 pm EDT.**
- ORISE personnel are available on-site for assistance.
  - **Reviewer Lab Hours:** Tuesday – Thursday, 7:30 am – 8:30 pm; Friday 7:30 am – 1:00 pm.
  - **Reviewer Lab Locations:**
    - Crystal Gateway Hotel—*Rosslyn Room* (downstairs, on Lobby level)
    - Crystal City Hotel—*Roosevelt Boardroom* (next to Salon A)
- Reviewers are invited to a brief feedback session – at 5:15 pm today, in this room.

## *H<sub>2</sub> Delivery Sub-Program*

**Sara Dillich (DOE Headquarters)**  
Production & Delivery Team Lead (acting)  
(202) 586-7925  
[sara.dillich@ee.doe.gov](mailto:sara.dillich@ee.doe.gov)

**Monterey Gardiner**  
*Mansfield Fellow for FY11 and FY12*

**Scott Weil (DOE Headquarters)**  
On Assignment from PNNL  
(202) 586-1758  
[kenneth.weil@hq.doe.gov](mailto:kenneth.weil@hq.doe.gov)

**Katie Randolph (Golden Field Office)**  
(720) 356-1749  
[katie.randolph@go.doe.gov](mailto:katie.randolph@go.doe.gov)

Support:

Kristine Babick (Energetics, Inc.)  
Angelo Cangialosi (Energetics, Inc.)  
Kim Cierpik (CNJV)

- **Analysis**

- ▶ ANL
- ▶ NREL
- ▶ PNNL
- ▶ Consultants

- **Forecourt Compression/Storage**

- ▶ NREL/Linde/AC Transit
- ▶ Fuel Cell Energy
- ▶ ORNL

- **H<sub>2</sub> Liquefaction & Liquid Delivery**

- ▶ Linde Corporation
- ▶ LLNL
- ▶ Prometheus Energy

- **Tube Trailer Delivery**

- ▶ Lincoln Composites
- ▶ LLNL

- **Pipelines & Pipeline Compression**

- ▶ Concepts NREC
- ▶ U.S. Department of Transportation
- ▶ I<sup>2</sup>CNER
- ▶ MITI
- ▶ NASA
- ▶ NIST
- ▶ ORNL
- ▶ SNL
- ▶ SRNL

- **Sub-program Review**

- ▶ BP
- ▶ Chevron
- ▶ ConocoPhillips
- ▶ U.S. Department of Transportation
- ▶ ExxonMobil
- ▶ Praxair
- ▶ Shell